



PERMINATOR TAPE (4" (101.6mm) STRIP CENTERED) (TO TERMINATE PERMINATOR)

MEL-PRIME

PERMINATOR (15 MILS) (MIN. 6" (152.4mm) TURNED UP WALL) (TERMINATE W/ TERM BAR & PERMINATOR TAPE IF REQ'D)

NOTE: DETAIL IS A GUIDE FOR INSTALLATIONS OF W. R. MEADOWS PRODUCTS ONLY. DETAIL MUST BE REVIEWED AND VERIFIED BY A DESIGN PROFESSIONAL FOR SUITABILITY ON THE PROJECT. W. R. MEADOWS DOES NOT ASSUME RESPONSIBILITY FOR ERRORS IN DESIGN OR ENGINEERING.

W. R. MEADOWS INC.
 300 INDUSTRIAL DR.
 HAMPSHIRE, IL 60140-0338
 1-800-342-5976



TITLE: **PERMINATOR UNDERSLAB TERMINATION @ BASE OF FOUNDATION WALL COND.2**

SCALE: **NTS** DWG NO.: **PERM-18**
 DATE: **MAY 14, 2024**